

Addendum 1, Solicitation No. 11-A006  
**CARROLL BUSINESS PARK, STREET A OVER BUFFALO CREEK TRIBUTARY,  
RFP No 2010051 (Solicitation 11-A006)**

The Carroll County Board of Commissioners submits Addendum 1 to **CARROLL BUSINESS PARK STREET A OVER BUFFALO CREEK TRIBUTARY, RFP No. 2010051 (Solicitation 11-A006)**. This addendum addresses questions and concerns discussed at the Pre-Bid meeting as well as other questions directed to the County.

CHANGES AND ADDITIONS TO ORIGINAL SOLICITATION

1. Proposals are still due 10:00 AM, Thursday, February 24, 2011.
2. Please review Attachment 1. This should clarify any questions or concern on the bid package.

All other Specifications, Terms and Conditions, not affected by the above changes and additions, remain in effect.

Bidders shall annotate receipt of this Addendum on the attachment. Proposals without this acknowledgement may be rejected.

R. Benedict  
Purchasing Manager  
(770) 830-5868  
[rbenedict@carrollcountyga.com](mailto:rbenedict@carrollcountyga.com)

February 21, 2011

---

**Request for Proposal for Carroll Business Park, Street A over Buffalo Creek Tributary  
RFP# 2010051 (Solicitation 11-A006) – Addendum #1**

---

Dear Mr. or Mrs.:

Below are items considered Addendum #1 to the RFP issued on 1/26/11 for the referenced project. This addendum is being issued to clarify questions that have been received.

1. The roadway contractor will stop the curb and gutter and roadway construction 100' from the end of the approach slab to leave room for the bridge construction. The roadway contractor will come back after the bridge is complete and finish the curb and gutter and roadway. No roadway work is included in the scope of this RFP.
2. The roadway contractor will not place the final topping on the roadway until the bridge construction is complete. No roadway work is included in the scope of this RFP.
3. There will be access to the bridge site from both sides of the creek. The southern access will be off of Martin Cemetery Road. The bridge contractor will be required to maintain the southern access road.
4. A temporary work bridge will be allowed provided that the construction limits remain unchanged. The wetland area must not be impacted beyond what is shown on the plans.
5. Conduits – the bridge plans show 10-6” diameter steel conduits. These conduits may be changed to the following:
  - a. Between beams 1 and 2 – 6-4” diameter Type D PVC Electrical Conduits
  - b. Between beams 5 and 6 – 4-6” diameter Bullet Proof Fiberglass Conduits

The bridge drawings will be revised prior to construction to show the updated conduit sizes.

The proponent must sign this Addendum below stating that it was received and the signed copy shall be submitted with the proposal.

Addendum #1 has been received and accepted:

---

Authorized Representative of Proponent